

Item	Description	Takeoff Qty	Labor		Material		Total
			Unit Cost	Amount	Unit Cost	Amount	Amount
03100.000 CONCRETE FORMS&ACCESSORSS							
03110.430	Forms in place, footings						
0500	Forms in place, rebar templates for footings or beams, 1 use	500.00 lf	2.07 /lf	1,035	0.76 /lf	380	1,415
1550	Forms in place, footings, keyway, 4 use, tapered wood, 2" x 6"	500.00 lf	0.55 /lf	275	0.27 /lf	135	410
	Forms in place, footings			1,310		515	1,825
	40.00 Labor hours						
03110.435	Forms place, grade beam						
0100	Forms in place, grade beam, plywood, 3 use	1,004.00 sfca	2.67 /sfca	2,681	0.63 /sfca	633	3,313
	Forms place, grade beam			2,681		633	3,313
	80.320 Labor hours						
03150.850	Accssrs,wall and foundatn						
3000	Accessories, form oil, coverage varies greatly, oil both sides	2.68 gal	-	-	6.60 /gal	18	18
	Accssrs,wall and foundatn					18	18
03150.860	Waterstop						
0850	Waterstop, PVC, dumbbell, 6" wide, 3/8" thick	500.00 lf	1.89 /lf	945	2.23 /lf	1,115	2,060
5200	Waterstop, field union, 3/8" x 6" wide	42.00 ea	5.50 /ea	231	19.55 /ea	821	1,052
	Waterstop			1,176		1,936	3,112
	34.31 Labor hours						
CONCRETE FORMS&ACCESSORSS				5,167		3,101	8,268
	154.63 Labor hours						
03200.000 CONCRETE REINFORCEMENT							
03210.600	Reinforcing in place						
0500	Reinforcing in place, A615 Gr 60, footings, #4 to #7	2.222 ton	580.01 /ton	1,289	760.00 /ton	1,689	2,978
	Reinforcing in place			1,289		1,689	2,978
	33.86 Labor hours						
CONCRETE REINFORCEMENT				1,289		1,689	2,978
	33.86 Labor hours						